

Procurements 2017

A photograph of a long, narrow aisle in a server room. The aisle is lined with rows of server racks on both sides. The racks are filled with server units, and many of them have glowing red and green lights. The floor is a light-colored, polished surface. The ceiling is a grid of metal panels with various cables and pipes running across it. The overall atmosphere is industrial and high-tech.

# National Supercomputer Centre at Linköping University

Niclas Andersson, Technical Director  
[nican@nsc.liu.se](mailto:nican@nsc.liu.se)

# Procurements 2017

Pre-announcement:

## Supercomputer **AC2018** (LiU-2017-02204)

- General computing resource for Swedish academic research
- Funded by Swedish National Infrastructure of Computing (SNIC).
- Replacing current SNIC-resource Triolith (and possibly LiUs Gamma) at NSC
- Contract size: 90 – 100 MSEK
- Installation in two phases at NSC during 2018.

## Supercomputer **NWP18** (LiU-2017-02205)

- Computing resource for daily numerical weather prediction for MetCoOp and climate research for MET Norway.
- Funded by Swedish Meteorological and Hydrological Institute (SMHI) and Norwegian Meteorological Institute (MET Norway).
- Replacing Frost(Bifrost), Alvin(Allvis), and Elvis(Allvis) at NSC.
- Contract size: 35 – 40 MSEK
- Installation of two systems at NSC (or NSC/SMHI) during 2018.

Pre-announcements, Benchmarks, Request for Information and an early draft of the Invitation to Tender are available at [www.nsc.liu.se/about/procurement](http://www.nsc.liu.se/about/procurement)



# Procurement Schedule

Procurement of AC2018 and NWP18 will be performed in parallel, just 1-2 weeks apart.

- 2017-06-15 – Pre-announcement
- 2017-07-10 – Invite to participate (30 days to answer)
- *2017-08-21* – Invite to tender (40-45 days to answer)
- *2017 Oct-Nov* – Negotiation
- *2017 Nov* – Contract

# Evaluation of Tenders

## Application performance / Cost

- Application Performance
  - Throughput performance of benchmarks
- Cost
  - Investment
  - Installation
  - Service & Support
  - Estimated power, cooling, and facility costs over four years.
  - Additional costs (e.g. complement cooling)

Performance and Cost will be validated at delivery.

# AC2018

- Will become the largest and fastest HPC resource in Sweden
- General purpose computing resource for researchers in Sweden
  - Focus on performance of the most used applications
  - Long-tail of legacy applications
- Benchmarks (reflects >50% of current usage):
  - VASP, Gromacs, CP2K
- Deliveries
  - Delivery #1: Central equipment and capacity on the level of current resource Triolith (currently 1017 dual socket SandyBridge)
    - Completely delivered and taken into production before 1 July 2018
  - Delivery #2: Extending the capacity.
    - After Triolith has been decommissioned
  - Optional:
    - Additional capacity, additional resource



# AC2018 Technical Details

- System Software: NSC Cluster System Environment (CSE) based on CentOS.
- Storage: Connect to existing storage
  - 4 x GSS26 (eight servers) from IBM/Lenovo running Spectrum Scale, Native RAID (GMR). Today connected to Triolith with IB FDR.
- Density: Minimum of 15 kW per (normal size) rack (peak).
- GPU: X% of the budget can be used for servers with GPUs if they achieve better performance on the VASP and Gromacs benchmarks.
  - A few GPUs for development.
- Large Mem: Approx. 5% of computing servers equipped with larger memory.
- Possible architectures:
  - CPU: Intel Xeon, Intel Xeon Phi, AMD Epyc, IBM Power9, ARM, ...
  - Network: Mellanox FDR, EDR, Intel OPA, Eth RoCE ...
  - Cooling: Air, Water, Immersed

# NWP18

- Main focus: Meteorological Co-operation on Operational Numerical Weather Prediction (MetCoOp)
  - Collaboration between SMHI, MET Norway and Finnish Meteorological Institutet (FMI).
  - Will be operative in late 2018.
  - NWP18 will be used together with a computing resource at FMI as a joint resource for HARMONIE-AROME Meteorological Ensemble Prediction System (MEPS) for the common regions of Sweden, Norway and Finland
- Benchmarks:
  - HARMONIE-AROME, NEMO
- Deliveries
  - System #1: Installation at NSC
  - System #2: Installation at NSC or SMHI.



# NWP18 Technical Details

- Two systems (System #1 at NSC, System #2 at NSC or SMHI):
  - System #1, part A: Daily Numerical Weather Prediction (MetCoOp)
  - System #1, part B: Climate Research (MET Norway)
  - System #2: Daily Numerical Weather Prediction (MetCoOp)
- System Software: NSC Cluster System Environment (CSE) based on CentOS.
- Storage: Connect to existing storage
  - 1 x GSS26 (eight servers) from Lenovo running Spectrum Scale, Native RAID. Today connected to Triolith with IB FDR.
  - Additional storage will be procured separately
- Density: Minimum of 15 kW per (normal size) rack (peak).
- SMHI computer room has a upper limit of 125 kW.  
(system 1A and 2 has to be diveded accordingly).
- Possible architectures:
  - CPU: Intel Xeon, Intel Xeon Phi, AMD Epyc, IBM Power9, ...
  - Network: Mellanox FDR, EDR, Intel OPA, Eth RoCE
  - Cooling: Air, (Water)





# Preliminary Requirements

(work in progress)



# Service & Support

## Requirements

- Installed equipment should be working and provide its intended service.
- Reduce and limit the time personnel at NSC spend on handling typical, recurring errors and failures (e.g. memory faults, PSUs failures) during the life-time of the system.
  - This include time spent on fault diagnostics, error reporting, ticket handling, logistics of parts (RMA handling), waiting for response, etc.
- The contractor is responsible for all advanced troubleshooting of equipment and components.
- Efficient escalation management to quickly resolve systematic errors



# Service & Support

## Service Levels

- Central or critical equipment
  - Spares on site and 4h or 8h response.
- The bulk of computing capacity
  - Minor faults affecting one server: replace within a week.
  - Major faults affecting half a rack or more: next business day

# Deliveries (suggestion)

## A Delivery

- Shipping and installation: 2 weeks
- Functional Tests: 2 – 4 weeks
  - acceptance testing
- Stability Test-period: 2 months
  - uptime, counting faults

## Deliveries

- Pre-delivery of solution samples for testing and porting
- Tetralith #1: March – June
  - Core parts + replacing Triolith capacity
- Tetralith #2: July – October
  - Extending capacity
- NWP18 System #1: May – August
  - Installation at NSC (about 60-70% of NWP18)
- NWP18 System 2: June – September
  - Installation at NSC or SMHI